



Notice of Work- Exterior Drilling & Testing

To: Capitol Building

From: Oregon State Capitol Renovation (OSCR) Team

Date: September 10, 2014

The following OSCR project team members will be working in the Capitol:

- 5-6 representatives from JE Dunn, GRI, and Dan J Fischer Excavating, Inc.

Scheduled Date and Time of Work:

- Thursday, September 18, 2014
- Friday, August 19, 2014
- Between the hours of 8:00 a.m. and 6:00 p.m. daily

Location of work:

- Northeast and Northwest side of the Capitol grounds.
- **Please see image below for detailed locations****

Work to be performed:

- Team members will be drilling three borings, each approximately 3 feet deep with a trailer-mounted drill rig.
- The drilling is anticipated to take approximately 4-6 hours to complete.
- Upon completion of the drilling, a 6 inch diameter PVC pipe will be installed in each of the three borings. Water will then be added to the pipes at each boring to test the saturation.
- The testing will be completed by the end of the day on Friday, September 19th. At that time, the holes will be backfilled.

Impacts:

- The team will be using a trailer-mounted drill rig to drill the three foot borings. The rig is pictured below.
- There will be some noise, similar to the sound of a generator, from the drill rig while the drilling is being performed.

Purpose of work:

- This work is required by the City of Salem in order to determine the amount of ground water the Capitol grounds can absorb and how much ground water will be sent to storm water drains. This information will be used in the design of the storm water system for the Capitol.

It is our goal to gather the above information in the most discreet method possible. Should any questions or concerns arise in the process of the work being conducted, we welcome you to contact us in Room 354 at 503.986.1190.

Thank you,

Jessica Lacasella

Project Communications Coordinator P: 503.986.1190 | Email: jessica.lacasella@state.or.us



Trailer-mounted drill rig

Site Plan Showing Proposed Boring Locations

